



Lobby Truss Structures

South Lobby

- Three truss structures located above the main escalators leading to Halls ABC
 - All are built using 12" white box truss
 - Stationary main structure is 118'W x 11'L
 - South side of the structure can be accessed using a Z34 boom lift from the Upper Mezzanine level.
 - North side of the structure can be accessed using a Z45 boom lift from the South Lobby, Howard Street side.
 - Truss is 18" from ceiling.
 - Two motorized trusses are each 20'W x 12"L. These are located in front of and behind the main stationary structure
- Weight Limits
 - Stationary Truss – 1,000lbs (uniform distribution) per 40' span.
 - Motorized Truss – 2,000lbs (uniform distribution) per 20' span
- Cost - \$5,000 plus labor charges as outlined below
 - Stationary Truss – Local 510 labor is responsible for installation and removal of banners. This labor is not included in the rental and should be arranged with the General Service Contractor.
 - Motorized Truss - Moscone Center Theatrical Services is responsible for lowering/raising the motorized truss. Labor cost for installation (8 straight time hours) and removal (8 straight time hours) is NOT included in the overall usage cost.
 - 24 hour notice is required to allow for scheduling of labor
 - Additional changes/moves will incur additional labor costs
 - Labor & Truss cost will be billed on final settlement
 - Local 510 labor is responsible for installation and removal of banners – this labor is not included in the above costs and should be arranged with the General Service Contractor



MOSCONE CENTER

SAN FRANCISCO | *moscone.com*

North Lobby

- 30'x12" white box truss with motors above escalators leading to Hall F
- Average banner size
 - 3'H x 30'W to 4'H x 30'W
 - Taller banners are not recommended as interior and exterior air conditions create a billowing effect on banners
- Weight Limit – 500lbs
- Cost - \$5,000 including labor as outlined below
 - Moscone Center Theatrical Services is responsible for lowering/raising the motorized truss. Labor cost for installation (8 straight time hours) and removal (8 straight time hours) is included in the overall usage cost
 - 24 hour notice is required to allow for scheduling of labor
 - Additional changes/moves will incur additional labor costs
 - Labor & Truss cost will be billed on final settlement
 - Local 510 labor is responsible for installation and removal of banners – this labor is not included in the above costs and should be arranged with the General Service Contractor

Use of truss structures must be arranged through the Moscone Center Event Manager.